## **Scope of Work**

Reference: DB7070 - City of New Braunfels (CONB) - Rd Improvement - Alves Ln, Comal County, TX

Enterprise Products is pleased to submit the following proposal for the installation of pipeline protection slab at Alves Ln as well as inspect, recoat and relocation of casing vent pipe at Floating Star Channel on 20" Line 9033-1 and 30" Line 177.

The scope of the project includes the following:

- inspect, recoat and install load bearing P/L protection slabs over two Enterprise Products pipeline 30" Line ID 177 and 20" Line ID 9033-1 at Alves Road, Comal County, TX. Refer to the drawings.
- inspect, recoat and move vent pipe to outside of the sidewalk over two Enterprise Products pipeline 30" Line ID 177 and 20" Line ID 9033-1 at Floating Star Channel. Refer to drawings of the vent pipe.
- redirect flow (as needed) while the retaining wall is down during construction
- provide adequate labor, supervision, equipment, and materials to prepare the line for inspection and recoat and installation of the protection slab and to moving of the vent pipe
- furnish all timber matting, trench box if required by site conditions or for pipeline protection
- dewatering any trenches, bell holes, launching pits, receiving pits, mud pits, pipe trenches, well points, pumps, and stone (for drainage), etc if determined as required that affect safe execution of the work
- backfill and restore construction site to original condition

## Note:

- 1) CONB will install & establish all vegetation, therefore, upon completion of the work described above, Enterprise's contractor will not be re-seeding or re-sodding.
- 2) CONB will rebuild walls and adjacent channel as part of their project. Therefore, upon completion of the work described above, Enterprise's contractor will backfill over the excavated area and build temporary measures to ensure positive drainage through the channel. CONB will install all permanent measures.