

Drawing Name: N:\Projects\LAN002.104 Arroyo Verde Unit 4--6\Planning\Plating\Arroyo Verde Unit 4-6 Plat.dwg User: MelanieMorris Aug 18, 2020 - 2:00pm

STATE OF TEXAS
COUNTY OF COMAL

I, THE UNDERSIGNED OWNER OF THE LAND SHOWN ON THIS PLAT, AND DESIGNATED HEREIN AS THE ARROYO VERDE SUBDIVISION UNIT 4 TO THE CITY OF NEW BRAUNFELS, COUNTY OF COMAL, TEXAS, AND WHOSE NAME IS SUBSCRIBED HERETO, DO HEREBY SUBDIVIDE SUCH PROPERTY AND DEDICATE TO THE USE OF THE PUBLIC ALL STREETS, ALLEYS, PARKS, DRAINS, EASEMENTS, AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSES AND CONSIDERATION THEREIN EXPRESSED.

OWNER:
ARROYO GOODWIN, LP
C/O MIKE LANCASTER
P.O. BOX 171004
SAN ANTONIO, TX 78217

STATE OF TEXAS
COUNTY OF COMAL

THIS INSTRUMENT WAS ACKNOWLEDGED BEFORE ME ON THIS ____DAY OF _____, 20____,

BY _____

NOTARY PUBLIC, STATE OF TEXAS
MY COMMISSION EXPIRES: _____

KNOW ALL MEN BY THESE PRESENTS:

I, THE UNDERSIGNED, DREW A. MAWYER, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECTLY MADE UNDER MY SUPERVISION AND IN COMPLIANCE WITH CITY AND STATE SURVEY REGULATIONS AND LAWS AND MADE ON THE GROUND AND THAT THE CORNER MONUMENTS WERE PROPERLY PLACED UNDER MY SUPERVISION.

DREW A. MAWYER
REGISTERED PROFESSIONAL LAND SURVEYOR NO. 5348
D.A. MAWYER LAND SURVEYING
5151 W. SH46
NEW BRAUNFELS, TEXAS 78132
FIRM #10191500



2021 SH 46W, Ste. 105
New Braunfels, TX 78132
ph : (8 3 0) 3 5 8 - 7 1 2 7
www.ma-tx.com TBPE FIRM F-13351

LEGEND:
P.O.B. = POINT OF BEGINNING
D.L. = DRAINAGE LOT
D.E. = DRAINAGE EASEMENT
U.E. = UTILITY EASEMENT
R.O.W. = RIGHT-OF-WAY
PAGE MATCH LINE
1/2" IRON PIN SET
IRON PIN FOUND
10' HIKE AND BIKE TRAIL

FINAL PLAT ESTABLISHING
ARROYO VERDE SUBDIVISION UNIT 4

BEING 24.900 ACRE OF LAND SITUATED IN THE ORILLA RUSSELL SURVEY NO. 2, ABSTRACT NO. 485, COMAL COUNTY, TEXAS, AND BEING OUT OF A REMAINING PORTION OF A CALLED 41.233 ACRE TRACT OF LAND AS CONVEYED TO ARROYO GOODWIN, LP, AND RECORDED IN DOCUMENT NO. 201606047502 OF THE OFFICIAL PUBLIC RECORDS OF COMAL COUNTY, TEXAS.


NOTES:

- ALL LOTS WITHIN THE SUBDIVISION WILL BE PROVIDED WATER, SEWER AND ELECTRIC BY NEW BRAUNFELS UTILITIES.
- ALL STREETS ARE PROPOSED TO BE OF A LOCAL TYPE FUNCTIONAL CLASSIFICATION WITH 50 FOOT RIGHT-OF-WAYS UNLESS NOTED OTHERWISE.
- SIDEWALK NOTES:
 - FOUR (4) FOOT WIDE SIDEWALKS WILL BE CONSTRUCTED BY THE HOME BUILDER PER CITY STANDARDS AT THE TIME OF BUILDING CONSTRUCTION, UNLESS OTHERWISE NOTED ON THE PLAT, ALONG:
 - ARROYO DORADO, ARROYO LOMA AND NISTER
 - FOUR (4) FOOT WIDE SIDEWALKS WILL BE CONSTRUCTED BY THE DEVELOPER PER CITY STANDARDS AT THE TIME OF SUBDIVISION STREET CONSTRUCTION ALONG:
 - ARROYO DORADO - LOT 900 BLOCK 1
- LOT 900, LOT 901 AND LOT 902 BLOCK 1 ARE DRAINAGE LOTS AND ARE NON-BUILDABLE LOTS. THESE LOTS WILL BE OWNED AND MAINTAINED BY THE PROPERTY OWNER'S ASSOCIATION, THEIR SUCCESSOR'S OR ASSIGNS, AND SHALL NOT BE THE RESPONSIBILITY OF THE CITY OF NEW BRAUNFELS OR COMAL COUNTY.
- THE SUBDIVISION IS WITHIN THE COMAL INDEPENDENT SCHOOL DISTRICT.
- ALL BEARINGS AND COORDINATES SHOWN HEREON ARE IN GRID BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, TEXAS SOUTH CENTRAL ZONE (4204), NORTH AMERICAN DATUM 1983. DISTANCES SHOWN HEREON ARE SURFACE USING COMBINED SCALE FACTOR OF 1.00015.
- MONUMENTS WERE FOUND OR SET AT EACH CORNER OF THE SURVEY BOUNDARY OF THE SUBDIVISION. MONUMENTS AND MARKERS WILL BE SET WITH 1/2" IRON PIN WITH PLASTIC CAP STAMPED "DAM #5348 PROP. COR." IMMEDIATELY AFTER COMPLETION OF UTILITY INSTALLATION AND STREET CONSTRUCTION UNLESS NOTED OTHERWISE.
- ARROYO VERDE SUBDIVISION UNIT 4, DOES FALL WITHIN THE CITY LIMITS OF THE CITY OF NEW BRAUNFELS.
- THE PROPOSED USE OF THE SUBDIVISION IS FOR SINGLE FAMILY RESIDENTIAL.
- ARROYO VERDE SUBDIVISION UNIT 4, ESTABLISHING A TOTAL OF 46 LOTS, WITH 44 BEING BUILDABLE.
- THIS SUBDIVISION IS SUBJECT TO THE 2006 CITY OF NEW BRAUNFELS PARK LAND AND DEDICATION ORDINANCE. THIS PLAT IS APPROVED FOR 1 DWELLING UNIT PER BUILDABLE LOT WITH A MAXIMUM OF 44 BUILDABLE LOTS. AT SUCH TIME THAT ADDITIONAL DWELLING UNITS ARE CONSTRUCTED; THE OWNER OF THE LOT SHALL CONTACT THE CITY AND COMPLY WITH THE ORDINANCE FOR EACH DWELLING UNIT.
- NO STRUCTURES, WALLS OR OTHER OBSTRUCTIONS OF ANY KIND SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT, NO LANDSCAPING, FENCES, OR OTHER TYPE OF MODIFICATIONS WHICH ALTER THE CROSS SECTIONS OF THE DRAINAGE EASEMENTS OR DECREASES THE HYDRAULIC CAPACITY OF THE EASEMENT, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE CITY ENGINEER. THE CITY OF NEW BRAUNFELS AND COMAL COUNTY SHALL HAVE THE RIGHT OF INGRESS AND EGRESS OVER GRANTORS ADJACENT PROPERTY TO REMOVE ANY OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS.
- THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORMWATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO STORMWATER CONVEYANCE STRUCTURES MUST HAVE A FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE A PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE GARAGE AND SHALL PREVENT WATER FROM LEAVING THE STREET.
- NO STRUCTURES IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO A PUBLIC WATER AND SEWER SYSTEM WHICH HAS BEEN APPROVED BY NEW BRAUNFELS UTILITIES.
- MAINTENANCE OF DRAINAGE EASEMENT DESIGNATED WITHIN A LOT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS ASSOCIATION.
- LOT 900 AND LOT 901 BLOCK 1 IS LOCATED WITHIN THE EXISTING SPECIAL FLOOD HAZARD ZONE A, 100-YEAR FLOOD BOUNDARY, AS DEFINED BY THE COMAL COUNTY, TEXAS COMMUNITY PANEL NUMBER 48091C0290F, REVISED NOVEMBER 02, 2009 AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY. NO OTHER PORTION OF THE SUBDIVISION IS LOCATED WITHIN THIS FLOOD BOUNDARY.

- EACH LOT OWNER SHALL BE RESPONSIBLE FOR VERIFYING THE DEPTH OF THE SEWER SERVICE STUB OUT AND DETERMINING THE MINIMUM SERVICEABLE FINISH FLOOR ELEVATION.
- NO PORTION OF THIS PROPERTY IS WITHIN THE EDWARDS AQUIFER RECHARGE ZONE.
- THIS SUBDIVISION IS LOCATED WITHIN THE TRANSITION ZONE OF THE AIRPORT HAZARD ZONING DISTRICT.
- SIDE ENTRY GARAGE SETBACK OF AT LEAST 20' WILL BE REQUIRED FOR CORNER LOTS (I.E. LOTS 13 AND 16 BLOCK 3; LOT 13 BLOCK 5; AND LOT 1, 5 AND 6 BLOCK 6).
- THIS SUBDIVISION IS SUBJECT TO THE NOTES, SPECIFICATIONS AND STANDRARDS STATED IN THE ARROYO VERDE PLANNED DEVELOPMENT DISTRICT MASTER PLAN APPROVED 12/5/2016 AND AS AMENDED PER ADMINISTRATIVE APPROVAL DATED 1/29/2019.
- SUBDIVISION IS SUBJECT TO THE DEVELOPMENT STANDARDS AS DEFINED IN ORDINANCE #2016-65 OF THE CITY OF NEW BRAUNFELS.
- THE ARROYO VERDE SUBDIVISION WILL HAVE A NEIGHBORHOOD PARK AND AMENITY CENTER THAT WILL BE OWNED AND MAINTAINED BY THE P.O.A. THE AMENITY CENTER AND PARK AREA WILL BE IN THE LOCATION SHOWN ON THE APPROVED MASTER PLAN.
- 2' CONTOURS ARE SOURCED FROM THE CITY OF NEW BRAUNFELS LIDAR GIS DATABASE AND ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, TEXAS SOUTH CENTRAL ZONE (4204), NORTH AMERICAN DATUM 1988.

NEW BRAUNFELS UTILITIES NOTES:

- MAINTENANCE OF DEDICATED UTILITY EASEMENTS IS THE RESPONSIBILITY OF THE PROPERTY OWNER. ANY USE OF AN EASEMENT, OR ANY PORTION OF IT, INCLUDING LANDSCAPING OR DRAINAGE FEATURES, IS SUBJECT TO AND SHALL NOT CONFLICT WITH THE TERMS AND CONDITIONS IN THE EASEMENT, MUST NOT ENDANGER OR INTERFERE WITH THE RIGHTS GRANTED BY THE EASEMENT TO NEW BRAUNFELS UTILITIES, ITS SUCCESSORS AND ASSIGNS, AND SHALL BE SUBJECT TO APPLICABLE PERMIT REQUIREMENTS OF THE CITY OF NEW BRAUNFELS OR ANY OTHER GOVERNING BODY. THE PROPERTY OWNER MUST OBTAIN, IN ADVANCE, WRITTEN AGREEMENT WITH THE UTILITIES TO UTILIZE THE EASEMENT, OR ANY PART OF IT.
- UTILITIES WILL POSSESS A 5' WIDE SERVICE EASEMENT TO THE BUILDING STRUCTURE ALONG THE SERVICE LINE TO THE SERVICE ENTRANCE. THIS EASEMENT WILL VARY DEPENDING UPON LOCATION OF DWELLING AND SERVICE.
- UTILITIES SHALL HAVE ACCESS TO THE METER LOCATIONS FROM THE FRONT YARD AND METER LOCATIONS SHALL NOT BE LOCATED WITHIN A FENCED AREA.
- EACH LOT MUST HAVE ITS OWN WATER AND SEWER SERVICE AT THE OWNER'S/DEVELOPER'S EXPENSE.
- DO NOT COMBINE ANY NEW UTILITY EASEMENTS (U.E.) WITH DRAINAGE EASEMENTS (D.E.) OR MAKE CHANGES IN GRADE WITHIN THE UTILITY EASEMENTS (U.E.) WITHOUT WRITTEN APPROVAL FROM NEW BRAUNFELS UTILITIES.



LOCATION MAP
SCALE: 1"=2,000'

APPROVED THIS THE _____ DAY OF _____, 20____ BY THE
PLANNING COMMISSION OF THE CITY OF NEW BRAUNFELS, TEXAS.

CHAIRMAN _____

APPROVED FOR ACCEPTANCE

DATE _____ PLANNING DIRECTOR _____

DATE _____ CITY ENGINEER _____

DATE _____ NEW BRAUNFELS UTILITIES _____

STATE OF TEXAS
COUNTY OF COMAL

I, _____, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT WAS
FILED FOR RECORD IN THE MAP AND PLAT RECORDS, DOC# _____ OF
COMAL COUNTY ON THE _____ DAY OF _____, 20____, AT _____ M.
WITNESS MY HAND OFFICIAL SEAL, THIS THE _____ DAY OF _____, A.D. 20____.



COUNTY CLERK, COMAL COUNTY, TEXAS

DEPUTY _____

Drawing Name: N:\Projects\LAN002.104 Arroyo Verde Unit 4-6 Plat.dwg User: MelanieMorris Sep 02, 2020 - 2:01pm

FINAL PLAT ESTABLISHING
ARROYO VERDE SUBDIVISION UNIT 4

BEING 24.900 ACRE OF LAND SITUATED IN THE ORILLA RUSSELL SURVEY NO. 2, ABSTRACT NO. 485, COMAL COUNTY, TEXAS,
AND BEING OUT OF A REMAINING PORTION OF A CALLED 41.233 ACRE TRACT OF LAND AS CONVEYED TO ARROYO GOODWIN,
LP, AND RECORDED IN DOCUMENT NO. 201606047502 OF THE OFFICIAL PUBLIC RECORDS OF COMAL COUNTY, TEXAS.



| CURVE TABLE | | | | | | |
|-------------|---------|---------|------------|---------|--------------|---------------|
| CURVE | LENGTH | RADIUS | DELTA | TANGENT | CHORD LENGTH | CHORD BEARING |
| C1 | 23.56' | 15.00' | 90°00'00" | 15.00' | 21.21' | N01°17'37"W |
| C2 | 23.56' | 15.00' | 90°00'00" | 15.00' | 21.21' | N88°42'23"E |
| C3 | 24.25' | 15.28' | 90°55'15" | 15.53' | 21.78' | S00°23'51"E |
| C4 | 9.72' | 125.00' | 4°27'16" | 4.86' | 9.72' | N48°23'14"E |
| C5 | 2.74' | 125.00' | 1°15'23" | 1.37' | 2.74' | N45°31'54"E |
| C6 | 7.49' | 175.00' | 2°27'12" | 3.75' | 7.49' | N44°56'00"E |
| C7 | 72.40' | 200.00' | 20°44'25" | 36.60' | 72.00' | N56°39'50"W |
| C8 | 36.20' | 100.00' | 20°44'25" | 18.30' | 36.00' | N56°39'49"W |
| C9 | 54.30' | 150.00' | 20°44'25" | 27.45' | 54.00' | N56°39'49"W |
| C10 | 54.30' | 150.00' | 20°44'25" | 27.45' | 54.00' | N56°39'50"W |
| C11 | 28.29' | 100.00' | 16°12'39" | 14.24' | 28.20' | N35°36'04"E |
| C12 | 28.29' | 100.00' | 16°12'40" | 14.24' | 28.20' | N35°36'04"E |
| C13 | 42.44' | 150.00' | 16°12'40" | 21.36' | 42.30' | N35°36'04"E |
| C14 | 18.57' | 150.00' | 7°05'31" | 9.30' | 18.55' | N49°50'28"W |
| C15 | 12.38' | 100.00' | 7°05'38" | 6.20' | 12.37' | N49°50'25"W |
| C16 | 18.57' | 150.00' | 7°05'38" | 9.30' | 18.56' | N49°50'25"W |
| C17 | 12.38' | 100.00' | 7°05'31" | 6.20' | 12.37' | N49°50'28"W |
| C18 | 306.31' | 65.00' | 270°00'01" | 65.00' | 91.92' | N01°17'37"W |
| C19 | 23.56' | 15.00' | 90°00'00" | 15.00' | 21.21' | N88°42'23"E |
| C20 | 19.32' | 15.00' | 73°47'21" | 11.26' | 18.01' | N09°23'56"W |
| C21 | 23.56' | 15.00' | 89°59'54" | 15.00' | 21.21' | N88°42'20"E |
| C22 | 23.56' | 15.00' | 90°00'06" | 15.00' | 21.21' | N01°17'40"W |
| C23 | 23.56' | 15.00' | 89°59'54" | 15.00' | 21.21' | N88°42'20"E |
| C24 | 2.61' | 125.00' | 1°11'49" | 1.31' | 2.61' | N44°18'18"E |

| LINE TABLE | | |
|------------|---------|-------------|
| LINE | LENGTH | BEARING |
| L1 | 18.53' | S46°17'37"E |
| L2 | 14.97' | N46°17'37"W |
| L3 | 55.00' | N46°17'37"W |
| L4 | 125.00' | N43°42'23"E |
| L5 | 110.00' | N46°17'37"W |
| L6 | 50.00' | N43°50'24"W |
| L7 | 6.97' | N50°36'51"E |
| L8 | 120.39' | S46°17'37"E |
| L9 | 83.38' | N87°53'51"E |
| L10 | 32.05' | S07°02'27"E |
| L11 | 58.76' | N46°17'37"W |
| L12 | 74.42' | N27°29'44"E |
| L13 | 89.88' | N27°29'44"E |
| L14 | 69.64' | N46°17'37"W |
| L15 | 77.13' | N46°17'43"W |
| L16 | 63.97' | N53°23'13"W |
| L17 | 25.00' | N46°17'37"W |
| L18 | 25.00' | N46°17'37"W |
| L19 | 63.97' | N53°23'13"W |
| L20 | 0.00' | N43°42'23"E |
| L21 | 27.29' | N43°42'17"E |
| L22 | 75.37' | N09°13'21"W |
| L23 | 50.58' | N57°31'10"W |
| L24 | 101.25' | N68°25'02"E |
| L25 | 113.58' | N68°25'02"E |
| L26 | 161.16' | N69°29'42"W |
| L27 | 50.00' | N20°30'18"E |

LEGEND:
P.O.B. = POINT OF BEGINNING
D.L. = DRAINAGE LOT
D.E. = DRAINAGE EASEMENT
U.E. = UTILITY EASEMENT
R.O.W. = RIGHT-OF-WAY
PAGE MATCH LINE
1/2" IRON PIN SET
IRON PIN FOUND
10' HIKE AND BIKE TRAIL

MOELLER & ASSOCIATES
Engineering Solutions
2021 SH 46W, Ste. 105
New Braunfels, TX 78132
ph: (830) 358-7127
www.ma-tx.com TBPE FIRM F-13351